

RFQ 14-00001 – Structured Cabling System
Questions & Clarifications
U.S. District Court for the District of Maryland

1. Communications Equipment Rack 4th Floor telephone closet – Will be provided by the selected cabling contractor per the specifications.
2. Wireless Access Point Cabling Requirements – the two wireless access point cable runs should be Category 6 terminating in Category 6 patch panels. There will be NO Category 6A cabling or equipment in the project scope.
3. Cabling routed above ceilings shall be supported using the following methods; in conduit where indicated on the drawings or on j-hooks. J-hooks to be provided by selected cabling contractor
4. While this is an active construction site ceiling bulkheads and tiles will be in place at the time of the structured cabling system install.
5. All infrastructure for structured cabling system is installed. It includes pull boxes stubbed above ceiling and ring and string.
6. New ring and string should be included on all runs.
7. After hours work timeframe is from 6:00 p.m. to 7:00 a.m.
8. All vertical cabling, floor box runs, and loud J-Hook installs will need to occur afterhours.
9. The speaker cable in Conference Room 4026 runs within the room from ceiling room center to a 6x6 wall mounted pull box in casework.
10. A security background check will be conducted by the U.S. Marshals for all on-site contractors.
11. Patch cables are included in the scope of the project.
12. Cooper backbone for analog fax lines installed according to specifications and documentation on the riser diagram.